

Main Office:

249 Jalan Boon Lay Singapore 619523 Tel: (65) 6660 7271 / (65) 6660 7322 Fax: (65) 6261 2617 Website: www.test.com.sg

E-mail: stsb@stengg.com (Regn. No.: 198004219D) Branch Office:

601 Rifle Range Road Singapore 588398 Tel: (65) 6460 9171 Fax: (65) 6469 3842

Block 4010 Ang Mo Kio Avenue 10 TECHPLACE 1 #01-11 & 03-08 - 03-12 Singapore 569626 Tel: (65) 6854 3571 / 3567 Fax: (65) 6854 3566

Report No:

16891-1114-03892-1-MEME

Date of Report:

25 November 2014

Page 1 of 8

Client's Reference:

Report Title:

Load Testing of 3-bay x 3-lift Modular Scaffoldings System

Client Details:

Kaoson Integrated Engineering Pte Ltd

18 Boon Lay Way, #09-163, Tradehub 21

Singapore 609966

Attn:

Mr. Jeffery Fong

Sample Description:

One set of 3-bay x 3-lift Galvanized Modular Scaffold System –

Scafom-rux RINGSCAFF System (Total approx. size: L7.71m x

W1.4m x H6.2m).

Tested For:

SAE Resources & Technologies Pte Ltd

Test Witnessed:

The above tests were witnessed by:

Mr. Jeffery Fong (Kaoson Integrated Engineering Pte Ltd) Mr. Prem N Tiwari (SAE Resources & Technologies Pte Ltd)

Mr. Antoine Nourisson (Scafom-rux Asia Ltd)

Test Standard:

Singapore Standard SS280: Part 2; 2009 "Specification for Metal."

Scaffoldings" - Part 2: Modular scaffoldings (Annex A)

Test Equipment:

ENERPAC PUMP with Cylinder RCH 202

Date of Receipt:

19 November 2014

Date of Test:

21 November 2014

Location of Test:

249 Jalan Boon Lay, Singapore 619523

Work Carried Out By:

Yong Soon Choy, Tan Yong Xiang & Tan Chee Kheng

Results Reported By:

Report Approved By:

Tan Yong Xiang

Testing Officer

Tan Chee Kheng

Supervisor

Materials Engineering Division



The results reported herein have been performed in accordance with the laboratory's terms of accreditation under the Singapore Accreditation Council – Singapore Laboratory Accreditation Scheme. Tests/ Calibrations marked "Not SAC SINGLAS Accredited" in this report are not included in the SAC- SINGLAS Accreditation Schedule for our laboratory.